

Take a look at our other products on our website



If you have any questions about your firepit

please contact us:-

hello@luxunique.co.uk

Luxunique Limited
Harbrook House
Wrexham Road
Nantwich
Cheshire
CW5 8ND

hello@luxunique.co.uk

www.luxunique.co.uk

Product Installation
Information
and Aftercare



Modular
Log Stores



Log Store Boxes Installation

Each box is delivered fully assembled ready to go. Simply create your own combination with the boxes and then secure together through the holes in the top and bottom using fixings supplied (as shown below).



We strongly recommend fixing the boxes to a solid wall or fence with suitable fixings using the brackets supplied. (As shown below). Please note wall/fence fixings are not supplied.



After installation any unused holes can be sealed with the remaining fixings if required.

Log Store Circles Installation

Each circle is delivered fully assembled ready to go. Simply create your own combination with the circles starting with the bases on the floor and then secure together through the holes in either side using fixings supplied (as shown below).



We strongly recommend fixing the circles to a solid wall or fence with suitable fixings using the brackets included. (As shown below). Please note wall/fence fixings are not supplied.



After installation any unused holes can be sealed with the remaining fixings if required.

Run Off

During the weathering process the Corten Steel produces carbon run off or staining to adjacent materials such as stone or concrete. To reduce any possible staining, we recommend raising the product up off the ground by placing it on a suitable slab of concrete which will prevent any direct contact with the flooring material and reduce the risk of any run off staining occurring.

After the initial reactive period the Corten will cure and self-seal, with little to no carbon run off. The weathering process of this product is integral to it and as such we will not accept any responsibility for damage caused to surrounding materials/ flooring as a result of carbon run off from any of our Corten Steel products. Please ensure that you do not place the product on any surface that may be damaged during the weathering process.

Step by Step Weathering Guide of Corten Steel

Stage 1 - Freshly manufactured Corten Steel. At this stage the dark oily residue coats the Corten Steel.

Stage 2 - The oily residue is beginning to break down, as the Corten Steel begins to weather.

Stage 3 & 4 - The "Run-Off" stage – This can take around 3-9 months depending on weather and positioning.

Stage 5 & 6 - The final stages of the weathering process. Some "Run-Off" may still occur as the Corten Steels patina develops to a striking, more consistent appearance.